

BILANS ROBÓT ZIEMNYCH – ulica Olszowa								
Pikieta	Pow. wykopu [m ²]	Pow. nasypu [m ²]	Odległość [m]	Obj. wykopu [m ³]	Obj. nasypu [m ³]	Całkowita obj. wykopu [m ³]	Całkowita obj. nasypu [m ³]	Obj. netto [m ³]
0+003.50	8.3	0.0	0.00	0.0	0.0	0.0	0.0	0.0
0+024.00	3.9	0.0	20.50	124.4	0.0	124.4	0.0	124.4
0+049.50	3.9	0.0	25.50	99.1	0.0	223.5	0.0	223.5
0+075.00	3.3	0.0	25.50	92.3	0.0	315.8	0.0	315.8
0+104.50	3.8	0.0	29.50	104.7	0.0	420.5	0.0	420.5
0+127.00	3.8	0.0	22.50	85.1	0.0	505.5	0.0	505.5
0+168.50	3.8	0.0	41.50	158.0	0.0	663.5	0.0	663.5
0+191.50	4.1	0.0	23.00	91.3	0.0	754.8	0.0	754.8
0+219.00	4.9	0.0	27.50	124.8	0.0	879.7	0.0	879.7
0+250.00	3.8	0.0	31.00	134.9	0.0	1014.6	0.0	1014.6
0+274.00	4.1	0.0	24.00	93.8	0.0	1108.4	0.0	1108.4
0+302.00	3.7	0.0	28.00	108.6	0.0	1217.0	0.0	1217.0
0+331.00	3.8	0.0	29.00	108.2	0.0	1325.2	0.0	1325.2
0+359.00	4.3	0.0	28.00	113.2	0.0	1438.4	0.0	1438.4
0+386.00	4.6	0.0	27.00	120.6	0.0	1559.0	0.0	1559.0
0+415.00	4.4	0.0	29.00	130.6	0.0	1689.6	0.0	1689.6
0+440.50	3.9	0.0	25.50	106.0	0.0	1795.6	0.0	1795.6
0+473.00	3.9	0.0	32.50	127.0	0.0	1922.6	0.0	1922.6
0+493.00	3.8	0.0	20.00	76.9	0.0	1999.5	0.0	1999.5
0+517.50	3.5	0.0	24.50	89.4	0.0	2088.9	0.0	2088.9
0+542.50	3.9	0.0	25.00	92.7	0.0	2181.6	0.0	2181.6
0+568.50	3.9	0.0	26.00	102.2	0.0	2283.8	0.0	2283.8
0+596.50	3.7	0.0	28.00	106.6	0.0	2390.4	0.0	2390.4
0+617.50	4.1	0.0	21.00	81.1	0.0	2471.5	0.0	2471.5
0+621.50	7.4	0.0	4.00	22.8	0.0	2494.3	0.0	<u>2494.3</u>

OBJĘTOŚĆ WYKOPU – **2494,3 m³**

OBJĘTOŚĆ ELEMENTÓW Z ROZBIÓRKI – 416,35m³ (bitum) + 31,68m³ (kostka betonowa) + 42m³ (płytki) + 37,35m³ (beton) + 57,06m³ (krawężniki) + 1,46m³ (obrzeża) = **585,9 m³**

OSTATECZNY BILANS ROBÓT ZIEMNYCH – 2494,3 m³ – 585,9 m³ = **1908,4m³**